



PROFILE VIEW

- NOTES:**
- IF SUBSTANTIAL BEDROCK IS ENCOUNTERED AND IT BECOMES NECESSARY TO BE REMOVED FROM CHANNEL FOR CONSTRUCTION OF THE BASE OF BOX CULVERT, WITH APPROVAL OF THE ENGINEER, THE BOX CULVERT AND VPI'S AT STA. 1+32 AND 1+72 SHALL BE RAISED A MAXIMUM OF 6" (3") WITH ADJUSTMENT TO ANT QUANTITIES PER COST. REMAIN AS SHOWN ON SHEET 5.
 - STA. 1+13 - 1+72 EXISTING CONCRETE LDV WATER STRUCTURE SHALL BE EXCAVATED AND ALL CONCRETE AND RUBBLE REMOVED FROM GOVERNMENT LAND.
 - STA. 0+42 (ONE LINE) AND 5+52 (TWO LINES) REMOVE EXISTING CSP AND DISPOSE OF OFF GOVERNMENT PROPERTY.
 - ALL DISTURBED GROUND, INCLUDING EXCESS EXCAVATION, SHALL BE SEEDED AND MULCHED.
 - ALL PAPER AGGREGATE THICKNESS FROM 8" THICK AT EACH END OF CONCRETE TO 4" THICK 25' AWAY FROM CONCRETE.

PLAN AND PROFILE VIEW

887pap.dwg

| | | |
|-----------------|-----------|--------------|
| OUACHITA | | |
| Road No. | Sheet No. | Total Sheets |
| 887 | 4 | 13 |

